KERALA STATE CIVIL SUPPLIES CORPORATION LTD MAVELI BHAVAN, PB NO.2030, GANDHI NAGAR, KOCHI-682020 Ph. No.0484-2207920

E-Mail: <u>ecp@supplycomail.com</u> Website: <u>www.supplycokerala.com</u>

No.D32-B/945/18

Dtd. 20.11.2020

QUOTATION NOTICE

The Kerala state Civil Supplies Corporation invites Quotation for "Providing additional toilet for ladies in third floor" which will be accepted up to 05.00 P.M on 18.12.2020 and opened on 21.12.2020, 02.00 P.M. For details and Quotation form please visit the website **"www.supplycokerala.com"**.

Sd/-Manager (E&CP)

//Approved for issue//

Asst. Manager (E&CP)

NAME OF WORK: PROVIDING ADDITIONAL TOILET FOR LADIES IN THIRD FLOOR OF HEAD OFFICE, SUPPLYCO								
QUOTATION								
SI.No.	Description of item	Qty	Unit	Rate	Amount			
1	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in-Charge.							
	Nominal concrete 1:4:8 leaner mix (including equivalent design mix)	0.25	Cum					
2	Dismantling PVC doors, etc including disposal of unserviceable surplus material and stacking of serviceable material with in 50 metres lead as directed by Engineer - in-Charge	3.20	Sqm					
3	Solid block masonry using pre cast solid blocks (Factory made) of size 30x20x15cm or nearest available size confirming to IS 2185 part I of 1979 for super structure above floor two level upto floor five level with thickness 15cm in : CM 1:6 (1 cement : 6 coarse sand) etc complete	1.00	Cum					
4	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts,buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor, etc. up to floor five level, excluding the cost of centering, shuttering and finishing:	1.00						
	1:3:6 (1 cement : 3 coarse sand :6 graded stone aggregate 20 mm nominal size)	0.25	Cum					
5	Plastering with 12 <i>mm cement plaster of mix:</i> 1:4 (1 <i>cement</i> : 4 <i>fine sand</i>) including cost and conveyance of all materials and all labour charges etc complete all as per the direction of Engineering Wing KSCSC.	0.50	Sqm					
6	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), including pointing the joints with white cement and matching pigment etc., complete.	4.00	Sqm					
7	Providing and fixing water closet squatting pan (Indian type W.C. pan) with 100 mm Sand Cast Iron P or S trap, 10 litter low level white P.V.C.flushing cistern, including flush pipe, manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever require:							
	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests	1	Each					

	Total :			
15	Supplying and fixing plumbing materials like fittings, etc			
12	Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer- in-Charge. Concealed work, including cutting chased and making good the wall etc. 110 mm pipe 6kgf/cm2	1.50	metre	
14		1.00	metre	
	Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer- in-Charge. Concealed work, including cutting chases and making good the wall etc. 75 mm pipe 6 Kgf/cm2	1.50	metre	
13		1.00	mouo	
12	Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer- in-Charge. Concealed work including cutting chases and making good the wall etc. 63 mm pipe 6 Kgf/cm2	1.50	metre	
11	Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer -in-Charge 20 mm dia 10 Kgf/cm2- Internal work - Exposed on wall	4.00	metre	
	15 mm nominal bore	1.00	Each	
10	Providing and fixing C.P brass bib cock of approved quality conforming to IS: 8931.			
9	Providing and fixing to existing door frames. 30 mm thick Glas Fibre Reinforced Plastic (FRP) panelled door shutter of required colour and approved brand and manufacture, made with fire - retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate for forming hollow rails and styles, with wooden frame and suitable blocks of seasoned wood inside at required places for fixing of fittings, cast monolithically with 5 mm thick FRP laminate for panels conforming to IS : 14856, including fixing to frames.	5.00	Sqm	
8	Providing and fixing Fiber Glass Reinforced plastic (FRP) Door Frames of cross- section 90 mm x 45 mm having single rebate of 32 mm x 15 mm to receive shutter of 30 mm thickness. The laminated shall be moulded with fire resistant grade unsaturated polyester resin and chopped mat. Door frame laminate shall be 2 mm thick and shall be filled with suitable wooden block in all the three legs. The frame shall be covered with fiber glass from all sides. M.S. stay shall be provided at the bottom to steady the frame.	14.50	Metre	