

“ഭരണഭാഷ - മാതൃഭാഷ”

നം.ഡി.32.B/1187/18

തീയതി.21.01.2021

കാട്ടേഷൻ നോട്ടീസ്

സപ്ലൈകോ കേന്ദ്രകാര്യാലയത്തിൽ മൂന്നാം നിലയിൽ ഒരു മാനേജർ ക്യാബിൻ നിർമ്മിക്കുന്നതിന് എംപാനല്ഡ് & ഗവ. അംഗീകൃത കോണ്ട്രാക്ടർമാരിൽ നിന്ന് കാട്ടേഷൻ ക്ഷണിക്കുന്നു.

NAME OF WORK : CONSTRUCTION OF CABIN FOR MANAGER (QA) IN THE THIRD FLOOR OF SUPPLYCO HEAD OFFICE

എസ്റ്റിമേറ്റ് തുക : RS.97,000/- (EXCL. GST)

വിശദ വിവരങ്ങൾ WWW.SUPPLYCOKERALA.COM എന്ന വെബ്സൈറ്റിലും കൂടാതെ എസ്റ്റേറ്റ്/ എഞ്ചിനീയറിംഗ് വിഭാഗങ്ങളിലും ലഭ്യമാണ്. കാട്ടേഷൻ സമർപ്പിക്കേണ്ട അവസാന തീയതി.30.01.2021, 5.00 PM

ഒപ്പ്/-
മാനേജർ (ഇ&സി.പി)

//അംഗീകാരത്തോടെ//

അസ്സി. മാനേജർ (ഇ&സി.പി)

- പകർപ്പ്-1. സീനിയർ എഞ്ചിനീയർ (സിവിൽ)
2. നോട്ടീസ് ബോർഡ്

NAME OF WORK: SUPPLYCO-ESTATE-HEAD OFFICE-PROVIDING GRILL FRAMES IN EXISTING OPENINGS FROM MIS SECTION TO GM'S CABIN AT H.O BUILDING

QUOTATION

| SI No | Description of Work | Qty | Unit | Rate | Amount (Bids. List) |
|-------|---|---------|------|------|------------------------|
| 1 | Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. angles, flats, square or round bars etc similar to existing window frame, including priming coat with approved steel primer, cost and conveyance of all materials and labour charges, scaffolding etc complete all as per the direction of Engineering Wing KSCSC. | | | | |
| | (i) Fixed to existing opening by means of drilling hold fasteners. | 1295.00 | Kg | | |
| 2 | Painting steel/wood work with two or more coats of SYNTHETIC ENAMEL PAINT of I quality and approved colour to give an even shade including cleaning the surfaces, filling the crevices with approved filler, scaffolding, etc complete all as per the direction of Engineering Wing KSCSC. | | | | |
| | (i) Two or more coats on new work | 60.00 | Sqm | | |
| 3 | Fixing hold fasteners on C.C. /R.C.C./Brick masonry surface backing including drilling necessary holes, chemical grouting for fixing hold fast, filling the crevices with approved filler, etc complete all as per the direction of Engineering Wing KSCSC. | 40.00 | each | | |
| | Total : | | | | |