

“ഭരണഭാഷ - മാതൃഭാഷ”

നം.ഡി.32.B/28991/16

തീയതി.30.11.2021

നോട്ടീസ്

സപ്ലൈകോ കേന്ദ്രകാര്യാലയത്തിലെ ഫസ്റ്റ് ഫ്ലോറിലെ സ്ത്രീകളുടെ ബാത്ത്റൂം വാതിലുകൾ റിപ്പയർ ചെയ്യുന്നതിനായി എംപാനൽഡ് കോൺട്രാക്ടർമാരിൽ നിന്ന് ക്വട്ടേഷൻ ക്ഷണിക്കുന്നു


NAME OF WORK: REPLACEMENT OF DOORS OF FIRST FLOOR LADIES TOILETS AT SUPPLYCO HEAD OFFICE

ESTIMATE: RS.32,000/- (EXCLUDING GST)

വിശദ വിവരങ്ങൾ [WWW.SUPPLYCOKERALA.COM](http://WWW.SUPPLYCOKERALA.COM) എന്ന WEBSITE ലും കൂടാതെ എസ്റ്റേറ്റ്/ എഞ്ചിനീയറിംഗ് വിഭാഗങ്ങളിലും ലഭ്യമാണ്. ക്വട്ടേഷൻ സമർപ്പിക്കേണ്ട അവസാന തീയതി.10.12.2021, 05.00 PM.

ഒപ്പ്/-  
മാനേജർ (ഇ&സി.പി)

//അംഗീകാരത്തോടെ//

  
അസി. മാനേജർ (ഇ&സി.പി)



Name of work: Replacing the existing doors of ladies toilet at first floor of Head office

Item No.	Description of item	Unit	Quantity	Rate to be quoted	Amount
1	Taking out doors, windows and clerestory window shutters (steel or wood ) including stacking within 50 metres lead:				
	Of area 3 sq. metres and below	Each	3.00		
2	Providing and fixing Fiber Glass Reinforced plastic (FRP) Door Frames of cross- section 90 mm x 45 mm having single rebate of 32 mm x 15 mm to receive shutter of 30 mm thickness. The laminated shall be moulded with fire resistant grade unsaturated polyester resin and chopped mat. Door frame laminate shall be 2 mm thick and shall be filled with suitable wooden block in all the three legs. The frame shall be covered with fiber glass from all sides. M.S. stay shall be provided at the bottom to steady the frame.	Metre	14.60		
3	Providing and fixing to existing door frames.				
	30 mm thick Glas Fibre Reinforced Plastic (FRP) panelled door shutter of required colour and approved brand and manufacture, made with fire - retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate for forming hollow rails and styles, with wooden frame and suitable blocks of seasoned wood inside at required places for fixing of fittings, cast monolithically with 5 mm thick FRP laminate for panels conforming to IS : 14856, including fixing to frames.	Sqm	4.881		
	<b>Total amount</b>				