

“ഭരണഭാഷ - മാതൃഭാഷ”

നം.ഡി.32.B/443/18

തീയതി.05.11.2022

നോട്ടീസ്

സപ്ലൈകോ കേന്ദ്രകാര്യാലയത്തിലെ ക്യാന്റിന് പുറത്ത് വശത്തെ പൊട്ടിയ ഡ്രെയിനേജ് സ്ലാബ് മാറ്റി പുതിയത് സ്ഥാപിക്കുന്നതിനായി താൽദൃമുള്ളവരിൽ നിന്നും ക്വട്ടേഷൻ ക്ഷണിക്കുന്നു

NAME OF WORK Replacing the broken drainage slab outside the canteen
with new one at Supplyco Head Office

Selling Estimate: Rs.26,000/- (EXCLUDING GST)

വിശദ വിവരങ്ങൾ WWW.SUPPLYCOKERALA.COM എന്ന WEBSITE ലും കൂടാതെ എസ്റ്റേറ്റ്/ എഞ്ചിനീയറിംഗ് വിഭാഗങ്ങളിലും ലഭ്യമാണ്. ക്വട്ടേഷൻ സമർപ്പിക്കേണ്ട അവസാന തീയതി.14.11.2022, 05.00 PM.

ഒപ്പ്/-
അഡീ. ജനറൽ മാനേജർ (ഇ&സി.പി)

//അംഗീകാരത്തോടെ//

അഡ്ഡി. മാനേജർ (ഇ&സി.പി)

Name of work : - SUPPLYCO - E&CP - Head Office - Replacing the broken drainage slabs outside the canteen with new one.

QUOTATION

Estimate Amount :- Rs. 26,000/-.

Item No	Quantity	Description of item	Unit	Rate	Amount
1 . Construction of Drainage slabs					
1.1	3.000	Engaging labours for taking out/relaying the existing drain cover and cleaning the drain for smooth flow of sullage & rain water, etc	each		
1.2	2.000	Labour Cleaning and clearing the site	each		
1.3	0.601	Demolishing R.C.C. work manually / by mechanical means including stacking of steel bars and disposal of unserviceable material with in 50 metres lead as per direction of Engineer -in-Charge.	cum		
1.4	5.601	Disposal of building rubbish/ malba/ similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approvedn by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved	cum		
1.5	2.000	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m.	cum		
1.6	0.601	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	cum		
1.7	0.400	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level:1:1:5:3 (1 cement 1.5 coarse sand :3 graded stone aggregate 20 mm nominal size	cum		
1.8	15.361	Centering and shuttering including strutting, etc. and removal of form for : Edges of slabs and breaks in floors and wallsUnder 20 cm wide	metre		
1.9	50.000	Steel reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete upto plinth levelThermo - Mechanically Treated bars of grade Fe-500D or more	kilogram		
1.10	4.000	12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	sqm		
TOTAL AMOUNT:					