

“ഭരണഭാഷ - മാതൃഭാഷ”

നം.ഡി.32.B/945/18

തീയതി.16.01.2023

നോട്ടീസ്

സപ്ലൈകോ കേന്ദ്രകാര്യാലയത്തിലെ ട്രാൻസ്ഫോർമറിന് ചുറ്റുമായി ഫെൻസിംഗ് ചെയ്യുന്നതിനായി കോൺട്രാക്ടർമാരിൽ നിന്നും ക്വട്ടേഷൻ ക്ഷണിക്കുന്നു

Name of Work :- Fencing work around the transformer at Supplyco compound (behind canteen)

Details of work:-

1. Earth work excavation for fixing angle frame to ground.
2. Fixing 2 inch angle frame with concreting.
3. Fencing with steel fabricated coated mesh of suitable size.
4. Scrapping & painting of one or more coat of enamel on frame.

Estimate for work :- Rs.61,000/- (excluding GST)

മെഷർമെൻറ് ഫോർമാറ്റ് സഹിതമുള്ള വിശദ വിവരങ്ങൾ WWW.SUPPLYCOKERALA.COM എന്ന WEBSITE ലും കൂടാതെ എസ്റ്റേറ്റ്/ എഞ്ചിനീയറിംഗ് വിഭാഗങ്ങളിലും ലഭ്യമാണ്. ക്വട്ടേഷൻ സമർപ്പിക്കേണ്ട അവസാന തീയതി.24.01.2023, 05.00 PM.

ഒപ്പ്/-
അഡീ. ജനറൽ മാനേജർ (ഇ&സി.പി)

//അംഗീകാരത്തോടെ//

അഡീ. മാനേജർ (ഇ&സി.പി)

Name of work : - SUPPLYCO - E&CP - Head Office - Transformer Fencing

QUOTATION

Estimate Amount :- Rs. 61,000/-

It. No.	Quantity	Description of item	Unit	Rate	Amount
1.1	5.55	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5m in width as well as 10 sqm on plan including disposal of excavated earth up to 50 m and lift up to 1.5 m, disposed soil to be levelled and neatly dressed:All Kinds of soil	sqm		
1.2	1.82	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level:1:2:4 (cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	Cum		
1.3	33.000	Providing and fixing angle iron frames for doors, windows and ventilators of mildsteel Angle sections of size 35x35x5 mm, joints mitred and welded by angle iron35x35x5 mm or 35x 5 mm flat pieces to the existing T-iron frame or to the wall withdash fastener, including fixing of necessary butt hinges and screws and applying	Kg		
1.4	51.00	Providing and fixing hard drawn coated steel wire fabric of size 75 x25 mm mesh or other suitable size wire mesh to be fixed & firmly anchored to the concrete surface by means of "L" shaped mild steel shear key welded with existing reinforcement including the cost of materials, labour, tool & plants as approved by Engineer-in-charge.	sqm		
1.5	21.24	Removing white or colour wash by scrapping and sand papering and preparingthe surface smooth including necessary repairs to scratches etc. complete	sqm		
1.6	21.240	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work	Sqm		
TOTAL AMOUNT:					

PTO