

“ഭരണഭാഷ - മാതൃഭാഷ”

നം.ഡി.32.A/354/23

തീയതി. .05.2023

നോട്ടീസ്

-

സപ്ലൈകോ കേന്ദ്രകാര്യലയത്തിലെ 2<sup>nd</sup> ഫ്ലോർ ലെ ബാൽക്കണി ഏരിയയിൽ Hand Rail വർക്ക് ചെയ്യുന്നതിനായി താൽപര്യമുള്ളവരിൽ നിന്നും ക്വട്ടേഷൻ ക്ഷണിക്കുന്നു

NAME OF WORK Provide Hand Rail for 2<sup>nd</sup> floor balcony area, minor repair works like refixing of loosened cladding tiles cleaning and clearing the weeds and rubbish from wall, and clearing of cracks seen on the surface.

Selling Estimate: Rs.45,000/- (EXCLUDING GST)

വിശദ വിവരങ്ങള് WWW.SUPPLYCOKERALA.COM എന്ന WEBSITE ലും കൂടാതെ എസ്റ്റേറ്റ്/ എഞ്ചിനീയറിംഗ് വിഭാഗങ്ങളിലും

ലഭ്യമാണ്. ക്വട്ടേഷൻ സമർപ്പിക്കേണ്ട അവസാന തീയതി. **12.06.2023, 05.00 PM.**

Signed by  
Sheeba George  
അഡീ. ജനറൽ മാനേജർ (ഇ&സി.പി)  
Date: 03-06-2023 16:05:57

**Name of work :- SUPPLYCO - E&CP - Head Office - G.I Hand Rail At HO 2 Floor.**

**QUOTATION**

**Estimate Amount :- Rs 45,000 Rupees Forty Five Thousand Only**

<b>It e</b>	<b>Description of item</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>
1	Providing and fixing hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approves steel primer.G.I. pipes	168.2	kg		
2	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade:Two or more coats on new work	18.75	sqm		
3	Providing and fixing double scaffolding system (cup lock type) on the exterior side, upto seven story hight made with 40 mm dia. M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staricase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required location with essential safety features for the workmen etc. complete as per directions and approval of Engineer- in Charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding. Note:- This item to be used for maintenance work judicially	10.5	sqm		
<b>2 Minor Repair &amp;Cleaning</b>					
2	Labour for cleaning and clearing of the site	1	each		
2	12 mm cement plaster of mix:1:4 ( 1 cement : 4 fine sand)	4	sqm		
2	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade:Two or more coats on new work	12	sqm		
2	Extra for providing and mixing water proofing material in cement plaster work in proportion recommended by the manufacturers.	120	kg		
	<b>Net Total Quantity</b>				
<b>3 Wall Tile</b>					
	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622(thickness to be specified by the manufacturer), of approved make, in all colours,shades except burgundy, bottle green, black of any size as approved by Engineerin-Charge,in skirting, risers of steps and dados, over 12 mm thick bed of cementmortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @3.3kg per sqm, including pointing in white cement mixed with pigment of matchingshade complete.	3	sqm		
	<b>Total</b>				