1/5493/2023

ഭരണഭാഷ - മാത്രഭാഷ"

No. KSCSC-1857/23-D32.B.ECP

<u>നോട്ടീസ്</u>

_

സപ്ലെകോ കേന്ദ്രകാര്യാലയത്തിലെ മൂന്നാമത്തെ നിലയിലെ അലൂമിനിയം വിൻഡോകൾ റിപ്പയർ ചെയ്യുന്നതിന് താൽപര്യമുള്ളവരിൽ നിന്നും ക്വട്ടേഷൻ ക്ഷണിക്കുന്നു

NAME OF WORK : Repair work of third floor

AluminiumWindow at supplyco

Head Office

Estimate Amount : Rs.77,000/- (EXCLUDING GST)

വിശദ വിവരങ്ങള് WWW.SUPPLYCOKERALA.COM എന്ന WEBSITE ലും കൂടാതെ എസ്റ്റേറ്റ് $^\prime$ എഞ്ചിനീയറിംഗ് വിഭാഗങ്ങളിലും ലഭ്യമാണ്. കുട്ടേഷന് സമർ പ്പിക്കേണ്ട അവസാന തീയതി. $06.10.2023,\,05.00~\mathrm{PM}.$

അഡീ. ജനറൽ മാനേജർ (ഇ&സി.പി)

Name of work : - Repair & Maintenance Of Aluminium Fabrication 3 Floor Supplyco HO, Kochi					
QUOTATION					
	Estimated Cost = Rs.77,000/-				
Item No.	Description of item	Quantity	Unit	Rate	Amount
1 Removal					
1.1	Skilled Labours for Roof Sheet, Truss works , Aluminium Fabrication and welding works.	8.00	each		
2 Repair					
2.1	Providing and fixing PTMT handles with				
	necessary screws etc. complete.150x34x24 mm		no		
	weighing not	5.00			
	less than 26 gms				
2.2	Providing and fixing aluminium tower bolts, ISI		no		
	marked, anodised(anodic coating not less than				
	grade AC	5.00			
	10 as per : 1868), transparent or dyed to				
	required colour or shade, with necessary screws				
2.3	Taking out existing aluminum partition (Included	18.72	Kg		
	Glazing or Particle board) work, repair and br>refixing				
	of repaired frames (Included Glazing or Particle				
	board), including replacement br>of hinges with				
	screws, EPDM Rubber wheels etc. as required,				
	all complete as per the direction of				
	the br>Engineer-incharge.				
3 Glazing					
	Providing and fixing glazing in aluminium door,				
3.1	window, ventilator shutters and partitions etc. with EPDM		Sqm		
	rubber / neoprene gasket etc. complete as per	20.00			
	the architectural drawings and the directions of				
	Engineer -				
	in -Charge. (Cost of aluminium snap beading				
	shall be paid in basic item):With float glass				
	panes of 4.0				
Imm thickness					
4.1	Providing and fixing aluminium work for doors,	5	Kg		
	windows, ventilators and partitions with extruded				
	built up				
	standard tubular sections/ appropriate Z sections and				
	other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of				
	required dia and size, including necessary filling up the				
	gans at junctions i.e. at ton hottom and sides with				
5 Re fixing					
5.1	Skilled Labours for Roof Sheet, Truss works ,	10	each		
	Aluminium Fabrication and welding works.				
6.1	6 Cleaning Labour for cleaning and clearing of the site	6	each		
0.1	7 Window Blinds		Cacii		
7.1	Providing and fixing roller blinds with coated and non-	18	Sqm		
	coated fabric, and light metal supported with				
	aluminium, screws and other sturdy components.				
	Total				
	10001				